



ELECTRICITY TRANSMISSION **230 KV K-2211 LOOP IN CONSTRUCTION**

LOCATION ▶ Newark, New Jersey

CUSTOMER ▶ PSEG

PROJECT SCOPE ▶

230 kV line transmission system upgrade.

START DATE ▶ July, 2015

FINISH DATE ▶ March, 2018

CHARACTERISTICS:

- ▶ Installed 8" and 10" pipes,
- ▶ Froze the circuits,
- ▶ Drained and cables were removed,
- ▶ Analyzed MFL smart pig of the pipe,
- ▶ Vacuumed and tested,
- ▶ Installed new Okonite cables,
- ▶ Spliced 230 kV USI joints, normal and phased joints,
- ▶ Fluid filled and pressure set up,
- ▶ Terminated 230 kV G&W potheads.





NORTH AMERICA

Newark, New Jersey
(United States)

ELECTRICITY TRANSMISSION
**230 KV K-2211
LOOP IN
CONSTRUCTION**

